

---

## TECHNICAL BULLETIN


---

### **WFT 2083 Now Warranted Up To 8 lbs. MVT or 90% RH**

Taylor 2083 Tuff-Lok X-Link VCT Adhesive is now warranted up to 8 lbs/1,000 ft<sup>2</sup>/24 hours moisture vapor transmission as measured by the anhydrous calcium chloride test in accordance with the test criteria set forth ASTM 1869. Taylor 2083 is also warranted up to 90% relative humidity as measured by the relative humidity test in accordance with the test criteria set forth in ASTM 2170. Please insure all test criteria is strictly followed as unreliable results may be obtained if strict accordance is not met. The minimum concrete slab age for the use of 2083 is 90 days. Taylor 2083 should not be used on any slab that is less than 90 days old. The pH of the concrete slab must be maintained between 5 and 9.

Any questions concerning the correct procedures for the placement or measuring of the above described test(s) should be directed to the calcium chloride test or relative humidity test manufacturer.

Regards,



Thomas F. Pope  
Manager – Technical Services

October 28, 2010